


Notes:

1. Minimum Dimensions of Concrete Pad Shown On Schedule.
2. Practical Distance From Wall To Be Applied Recommend 250mm.
3. Condensate From Unit Needs To Be Either Absorbed By Surrounding Area If Over Garden Area Or Alternatively Aco Drain Can Be Installed Around The Perimeter Of the Concrete Pad.

Chofu Heat Pumps (mm)

	6kW	10kW	16kW
A	750	750	750
B	300	330	330
C	210	230	255
D	580	540	590
E	1000	1000	1100

CHNZ	TITLE:	Chofu Heat Pump Installation Concrete Pad Sizing			 Central Heating NEW ZEALAND 3 Enterprise Avenue Christchurch Ph: (03) 357-1233 Fax: (03) 343-1236 www.centralheating.co.nz	DRAWN:	CHNZ	Project No:	-	
						CHECKED:	CHNZ	SHEET:	1 of 1	
						DESIGN:	CHNZ	SCALE:	1:10@A3	
						DATE:	10 APR 2026	DRG No.	HPC	ISSUE: A
	Issue	Date	Amendment							